

AD-A104 952

PRC CONSOER TOWNSEND INC ST LOUIS MO

F/6 13/13

NATIONAL DAM SAFETY PROGRAM. INCLINE VILLAGE LAKE DAM (MO 11041--ETC(U)

SEP 80 W 6 SHIFRIN


DACW43-80-C-0094

NL

UNCLASSIFIED

1 OF 2

AD-A  
104 952



LEVEL

①

## MISSISSIPPI-SALT-QUINCY RIVER BASIN

AD A104952

INCLINE VILLAGE LAKE DAM  
ST. CHARLES COUNTY, MISSOURI  
MO. 11041

"Original contains color  
plates: All DTIC reproductions  
will be in black and  
white"

# PHASE I INSPECTION REPORT NATIONAL DAM SAFETY PROGRAM



United States Army  
Corps of Engineers

... Serving the Army  
... Serving the Nation

**St. Louis District**

DTIC  
ELECT  
OCT 6 1981  
H

PREPARED BY: U. S. ARMY ENGINEER DISTRICT, ST. LOUIS

FOR: STATE OF MISSOURI

DISTRIBUTION STATEMENT A

Approved for public release;  
Distribution Unlimited

Original contains color  
plates: All DTIC reproductions  
will be in black and  
white

SEPTEMBER, 1980

81 10 2 152

FILE COPY

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
	AD A304952	
4. TITLE (and Subtitle) Phase I Dam Inspection Report National Dam Safety Program Incline Village Lake Dam (MO 11041) St. Charles County, Missouri		5. TYPE OF REPORT & PERIOD COVERED 9 Final Report
7. AUTHOR(s) Consoer, Townsend and Associates, Ltd.		6. PERFORMING ORG. REPORT NUMBER
		8. CONTRACT OR GRANT NUMBER(s) 15 DACW43-80-C-0094
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS 110
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		12. REPORT DATE September 1980
		13. NUMBER OF PAGES Approximately 105
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) 6 National Dam Safety Program. Incline Village Lake Dam (MO 11041), Mississippi - Salt - Quincy River Basin, St. Charles County, Missouri. Phase I Inspection Report.		15. SECURITY CLASS. (of this report) UNCLASSIFIED
16. DISTRIBUTION Approved for release; distribution unlimited. 16 Walter G/Sr Frin		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE 12 104
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety, Lake, Dam Inspection, Private Dams		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report was prepared under the National Program of Inspection of Non-Federal Dams. This report assesses the general condition of the dam with respect to safety, based on available data and on visual inspection, to determine if the dam poses hazards to human life or property.		

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

412 553

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)



REF ID: A66666

DEPARTMENT OF THE ARMY  
ST. LOUIS DISTRICT, BUREAU OF ENGINEERS  
210 TUCKER BOULEVARD, NORTH  
ST. LOUIS, MISSOURI 63101

SUBJECT: Incline Village Lake Dam (Mo. 11041) Phase I Inspection Report

This report presents the results of field inspection and evaluation of the Incline Village Lake Dam (Mo. 11041).

It was prepared under the National Program of Inspection of Non-Federal Dams.

**SIGNED**

SUBMITTED BY: \_\_\_\_\_  
Chief, Engineering Division

**15 OCT 1980**

\_\_\_\_\_  
Date

**SIGNED**

APPROVED BY: \_\_\_\_\_  
Colonel, CE, District Engineer

**15 OCT 1980**

\_\_\_\_\_  
Date

Accession	
Exempt	
Index	
Uncl	
Class	
By	
Distribution	
Availability Codes	
Availability	
Dist	Special
A	

INCLINE VILLAGE LAKE DAM  
ST. CHARLES COUNTY, MISSOURI

MISSOURI INVENTORY NO. 11041

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

PREPARED BY  
CONSOER, TOWNSEND AND ASSOCIATES, LTD.  
ST. LOUIS, MISSOURI  
AND  
PRC ENGINEERING CONSULTANTS, INC.  
ENGLEWOOD, COLORADO  
A JOINT VENTURE

UNDER DIRECTION OF  
ST. LOUIS DISTRICT, CORPS OF ENGINEERS  
FOR  
GOVERNOR OF MISSOURI

SEPTEMBER 1980

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

Name of Dam: Incline Village Lake Dam, Missouri Inv. No. 11041  
State Located: Missouri  
County Located: St. Charles  
Stream: Indian Camp Creek  
Date of Inspection: April 23, 1980

Assessment of General Condition

Incline Village Lake Dam was inspected by the engineering firms of Consoer, Townsend and Associates, Ltd. and PRC Engineering Consultants, Inc. (A Joint Venture) of St. Louis, Missouri, according to the U. S. Army Corps of Engineers' "Engineer Regulation No. 1110-2-106" and additional guidelines furnished by the St. Louis District of the Corps of Engineers. Based upon the criteria in the guidelines, the dam is intermediate in size and it is in the high hazard potential classification, which means that urban development with more than a small number of habitable structures could be affected in the event of failure of the dam. Within the estimated damage zone of six miles downstream of the dam are three dwellings, a highway (U.S. Hwy 61), and a light duty road and bridge that may be subjected to flooding, with possible damage and/or destruction, and possible loss of life.


The dam appears to be in satisfactory condition. However, several deficiencies were noted by the inspection team that could affect the safety of the dam. Our inspection and evaluation indicates that the spillway of Incline Village Lake Dam

does not meet the criteria set forth in the guidelines for a dam having the above size and hazard potential. Incline Village Lake Dam being an intermediate size dam with a high hazard potential is required by the guidelines to pass the Probable Maximum Flood without overtopping. It was determined that the reservoir/spillway system can accommodate approximately 60 percent of the Probable Maximum Flood without overtopping the dam. Our evaluation also indicates that the reservoir/spillway system can accommodate the one-percent chance flood without overtopping.

The Probable Maximum Flood is defined as the flood discharge that may be expected from the most severe combination of critical meteorological and hydrologic conditions that are reasonably possible in the region.

Other deficiencies noted by the inspection team were: areas of what appeared to be seepage observed approximately 75 to 100 feet downstream of the toe, erosion areas located in the downstream contact areas of both abutments and on the downstream slope, the lack of surface erosion protection on the downstream slope, the beginnings of a vegetative growth among the upstream riprap, fractures in the spillway crest, conditions of mild leakage in the 24-inch valve connected to one of the low level drain pipes, a need for periodic inspection by a qualified engineer, and a lack of a maintenance schedule. The lack of seepage and stability analyses on record is also a deficiency that should be corrected.

It is recommended that the owner take action to correct or control the deficiencies described above.



Walter G. Shifrin, P.E.







Overview of Inclined Village Lake Dam

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

INCLINE VILLAGE LAKE DAM, I.D. No. 11041

TABLE OF CONTENTS

<u>Sect. No.</u>	<u>Title</u>	<u>Page</u>
SECTION 1	PROJECT INFORMATION . . . . .	1
	1.1 General . . . . .	1
	1.2 Description of Project . . . . .	3
	1.3 Pertinent Data . . . . .	8
SECTION 2	ENGINEERING DATA . . . . .	10
	2.1 Design . . . . .	10
	2.2 Construction . . . . .	11
	2.3 Operation . . . . .	11
	2.4 Evaluation . . . . .	12
SECTION 3	VISUAL INSPECTION . . . . .	14
	3.1 Findings . . . . .	14
	3.2 Evaluation . . . . .	22

TABLE OF CONTENTS

(Continued)

<u>Sect. No.</u>	<u>Title</u>	<u>Page</u>
SECTION 4	OPERATION PROCEDURES . . . . .	24
	4.1 Procedures . . . . .	24
	4.2 Maintenance of Dam . . . . .	24
	4.3 Maintenance of Operating Facilities . . . . .	24
	4.4 Description of Any Warning System in Effect . . . . .	25
	4.5 Evaluation . . . . .	25
SECTION 5	HYDRAULIC/HYDROLOGIC . . . . .	26
	5.1 Evaluation of Features . . . . .	26
SECTION 6	STRUCTURAL STABILITY. . . . .	31
	6.1 Evaluation of Structural Stability. . . . .	31
SECTION 7	ASSESSMENT/REMEDIAL MEASURES. . . . .	34
	7.1 Dam Assessment . . . . .	34
	7.2 Remedial Measures. . . . .	36

## TABLE OF CONTENTS

(Continued)

## LIST OF PLATES

	<u>Plate No.</u>
LOCATION MAP . . . . .	1
PLAN, AND SECTIONS OF DAM . . . . .	2
DESIGN DRAWINGS . . . . .	3-4
GEOLOGIC MAP . . . . .	5-6
SEISMIC ZONE MAP . . . . .	7

## APPENDICES

APPENDIX A	-	PHOTOGRAPHS
APPENDIX B	-	HYDROLOGIC AND HYDRAULIC COMPUTATIONS

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

INCLINE VILLAGE LAKE DAM, Missouri Inv. No. 11041

SECTION 1: PROJECT INFORMATION

1.1 General

a. Authority

The Dam Inspection Act, Public Law 92-367 of August, 1972, authorizes the Secretary of the Army, through the Corps of Engineers, to initiate a national program of dam inspections. Inspection for Incline Village Lake Dam was carried out under Contract DACW 43-80-C-0094 between the Department of the Army, St. Louis District, Corps of Engineers, and the engineering firms of Consoer, Townsend & Associates, Ltd., and PRC Engineering Consultants, Inc. (A Joint Venture), of St. Louis, Missouri.

b. Purpose of Inspection

The visual inspection of Incline Village Lake Dam was made on April 23, 1980. The purpose of the inspection was to make a general assessment as to the structural integrity and operational adequacy of the dam embankment and its appurtenant structures.

c. Scope of Report

This report summarizes available pertinent data relating to the project, presents a summary of visual observations made during the field inspection, presents an assessment of hydrologic and hydraulic conditions at the site, presents an assessment of the structural adequacy of the various project features and assesses the general condition of the dam with respect to safety.

Subsurface investigations, laboratory testing and detailed analyses were not within the scope of this study. No warranty as to the absolute safety of the project features is implied by the conclusions presented in this report.

It should be noted that in this report reference to left or right abutments is viewed as looking downstream. Where left abutment or left side of the dam is used in this report, this also refers to the north abutment or side, and right to the south abutment or side.

d. Evaluation Criteria

The inspection and evaluation of the dam is performed in accordance with the U.S. Army Corps of Engineers, "Engineer Regulation No. 1110-2-106" and additional guidelines furnished by the St. Louis District office of the Corps of Engineers for Phase 1 Dam Inspection.

## 1.2 Description of the Project

### a. Description of Dam and Appurtenances

The following description is based upon design drawings, observations and measurements made during the visual inspection and from conversations with Mr. Larry Bade, a representative of the firm which designed and supervised the construction of the dam. Any discrepancies between the design drawings and our field measurements will be noted. The design drawings are included in this report.

The dam is a zoned, rolled, earthfill structure with a straight alignment between rock abutments. (Photo overview). According to the drawings, the embankment was supposed to be a homogeneous fill; however, according to Mr. Bade, the dam was constructed with three different zones. The dam was constructed with a core of a good clay material, an upstream shell of a poorer clay material and a downstream shell of a sandy gravel. The top of dam width is 45 feet and the axis length of the crest of the embankment was measured as 856 feet. There is a distance of approximately 64 feet between the right abutment and the left wall of the spillway discharge channel. This gives a total length of 920 feet from the left abutment contact to the edge of the spillway channel. The top of dam elevation at the maximum section is 530 feet above M.S.L. The top of dam is fairly level between the left abutment and a point approximately 570 feet to right; however, from this point to the right abutment there is a gradually increasing slope, which decreases the elevation by 4.4 feet (See Plate 2). The upstream slope is 1V to 3H and is protected by riprap. A 15-foot wide bench was constructed on the upstream slope at an elevation of approximately 518 feet above M.S.L. The downstream slope is 1V to 3H. Piles of riprap

approximately 4 feet high were placed at the downstream toe and a 50 foot wide, approximately 2 foot thick, blanket of riprap was placed along the downstream toe to protect the toe from discharges through the spillway. The maximum height of the dam was measured as 38 feet above creekbed elevation.

There is one spillway constructed at the damsite and a low level drain system. The spillway, therefore, serves as both an emergency spillway for larger flows and a principal spillway for the normal flows. The spillway crest and adjacent channel area were blasted out of rock just to the right of the right abutment. The maximum section top of dam is at assumed elevation 530; using field measurements the spillway crest is at elevation 510.7 and the spillway discharge channel, immediately adjacent to the spillway crest, is at elevation 497, i.e., there is approximately a 14-foot drop at the crest. The length of this rock spillway crest is approximately 246 feet. After the water drops over the crest, it falls into an approximately 200 foot wide pool area just before entering the 100 foot wide discharge channel. The spillway crest is more or less rough hewn, and is semi-circular in shape; the water was flowing over on the left side only, on the day of the inspection. This means that the entire length of the crest is not all at the same elevation; however, the design representative has indicated that they expect to construct a rectangular weir on top of the existing crest, except that it will be set back about 15 feet. According to Mr. Bade the weir crest will be set at elevation of 517.5 feet above M.S.L. and will have a length of approximately 255 feet.

A low level drain was provided for the dam. The drain consists of two 22 inch diameter welded steel pipes which pass through the embankment side by side. Each pipe is controlled at the downstream end by a 24 inch gate valve.



According to Mr. Bade, each pipe was provided with three 6-foot square seep collars made of 1/4-inch thick steel plate; the elevation at the intake of each pipe is different. One of the pipes has an intake elevation of 500 feet above M.S.L. with no bends in the pipe. The other pipe has an intake elevation of 510 feet above M.S.L. with a 10-foot high standpipe. Both pipes run parallel to each other from the outlet to the 500 foot elevation, at which point, one of the pipes stops and the other pipe continues with the 10-foot high standpipe connected to it. The outlet elevation is approximately 497 feet above M.S.L. No screen or trashrack was provided on the pipes. The pipes discharge into an approximately 75-foot long riprapped discharge channel which is perpendicular to the dam and connects to the discharge channel of the spillway. The drain is located approximately 400 feet to the right of the left abutment.

b. Location

Incline Village Lake Dam is located in the state of Missouri, St. Charles County, across Indian Camp Creek, a tributary to Big Creek, which is in turn tributary to the Cuivre River. The damsite is approximately 6 miles south of Moscow Mills, a community on the Cuivre River, and can be found on the 7.5 minute series of the Foristell, Mo. Quadrangle, in Range 1 East, Township 47 North.

c. Size Classification

According to the "Recommended Guidelines for Safety Inspection of Dams" by the U.S. Department of the Army, Office of the Chief Engineer, the dam is classified in the dam-size category as being "Intermediate" since its storage is more than 1,000 acre-feet but less than 50,000 acre-feet. The dam

would be classified as "Small" in the dam-size category because its height is more than 25 feet and less than 40 feet; however, the overall size classification is "Intermediate".

d. Hazard Classification

The dam has been classified as having a "High" hazard potential in the National Inventory of Dams, on the basis that in the event of failure of the dam or its appurtenances, excessive damage could occur to downstream property, together with the possibility of the loss of life. Our findings concur with the classification. Within the estimated damage zone, which extends approximately six miles downstream of the dam, are three dwellings, a U.S. Highway, and a light-duty road and bridge.

e. Ownership

Incline Village Lake Dam is owned by Incline Investment Inc. The mailing address is Incline Investment Inc., c/o Mr. Clarence Tiemeyer, 4051 Cypress Road, St. Ann, Missouri, 63074.

f. Purpose of Dam

The purpose of the dam is to impound water for recreational use as a private lake.

g. Design and Construction History

Incline Village Lake Dam was planned and designed by Lewis and Associates of Warrenton, Missouri between 1974 and 1978. A set of plans has been made available for this report.

The dam was built between August 1977 and April 1978 by Hunt Excavating of Warrenton, Missouri, and Hutchison and Schaeffer. Mr. Larry Bade, who was the project engineer for Lewis and Associates, supervised and coordinated the construction of the dam. The construction of the dam was halted in December 1977 in order to obtain a U.S. Army Corps of Engineers Section 404 Permit for the dam.

The spillway was widened approximately 60 to 70 feet and deepened between December 1979 and February 1980. A rock berm was excavated from the north side of the spillway as part of the widening process. The purposes of the spillway widening were to provide rock aggregate for the lake development roads and also to increase the capacity of the spillway.

h. Normal Operational Procedures

Incline Village Lake Dam is used to impound water for recreational use. Normal procedures is to allow the lake level below the spillway crest to remain as high as rainfall, runoff, evaporation and seepage will allow.

1.3      Pertinent Data

a.    Drainage Area (square miles): . . . . . 27

b.    Discharge at Damsite

Estimated experienced maximum flood (cfs): . . . . . NA

Estimated existing ungated spillway capacity  
with reservoir at minimum top of dam elevation (cfs): . . . . . 43,724

c.    Elevation (feet above MSL)

Top of dam (minimum): . . . . . 525.6

Spillway crest: . . . . . 510.7

Normal Pool: . . . . . 510.7

Maximum Experienced Pool: . . . . . NA

Observed Pool: . . . . . 510.7+

d.    Reservoir

Length of pool with water surface  
at minimum top of dam elevation (feet): . . . . . 18,000

e.    Storage (Acre-Feet)

Top of dam (minimum): . . . . . 3064

Spillway crest: . . . . . 684

Normal Pool: . . . . . 684

Maximum Experienced Pool: . . . . . NA

Observed Pool: . . . . . 684

f.    Reservoir Surfaces (Acres)

Top of dam (minimum): . . . . . 255

Spillway crest: . . . . . 90

Normal Pool: . . . . . 90

Maximum Experienced Pool: . . . . . NA

Observed Pool: . . . . . 90+

g. Dam

Type: . . . . . Earthfill  
 Length: . . . . . 856 feet  
 Structural Height: . . . . . 58 feet  
 Hydraulic Height: . . . . . 38 feet  
 Top width: . . . . . 45 feet  
 Side slopes:  
     Downstream . . . . . 1V to 3H  
     Upstream . . . . . 1V to 3H  
 Zoning: . . . . . Core, Upstream (mostly clay)  
                                     Downstream (mostly sandy gravel)  
 Impervious core: . . . . . Clay  
 Cutoff: . . . . . Core trench excavated to bedrock  
 Grout curtain: . . . . . None

h. Diversion and Regulating Tunnel                      None

i. Spillway

Type:                      vertical drop with rectangular and  
                                     trapezoidal open channel, uncontrolled  
 Length of crest:                      246 feet  
 Crest Elevation (feet above MSL);                      510.7

j. Regulating Outlets

Type:                      Two, 22-inch diameter  
                                     low-level drains  
 Length:                      1 @ 240+  
                                     1 @ 150+  
 Closure:                      Gate valves

## SECTION 2: ENGINEERING DATA

### 2.1 Design

A limited set of drawings for Incline Village Lake Dam has been made available from the engineering firm of Lewis and Associates of Warrenton, Missouri. The following engineering data and information were also available for the dam:

- 1) Application for Department of the Army Permit Form 4345.
- 2) Vicinity Map.
- 3) Qualifications of the Engineers Working on the Project.
- 4) Environmental Assessment Report.
- 5) Engineering Study for the Lake and Dam.
- 6) Copy of Plan for the Dam (Included as Plate 3 & 4 in this report).
- 7) Soil Boring Log for a Damsite for Incline Village Lake Dam. (Site was approximately 500 feet east of the existing dam).

8) Joint Public Notice by U.S. Army Corps of Engineers and State of Missouri for an After-The-Fact Department of the Army Permit to Construct the Dam.

9) Engineering Geologic Report on Sugar Valley Dam, (Incline Village Lake Dam) St. Charles, Missouri.

## 2.2 Construction

According to Mr. Bade, a core trench was constructed as shown on the design drawings; the core trench had a 10-foot wide bottom and was excavated to bedrock with a maximum depth of approximately 20 feet. Compaction was achieved by the fact that the embankment was brought up in 6 inch layers combined with the activity of the earthmoving equipment used for the placement of the fill. No compaction tests were performed. The two clay materials used for the embankment were removed from the reservoir area and the left abutment area. The sandy gravel was the material removed from the core trench. Also, according to Permit Form 4345, mentioned in paragraph 2.1 above, material for the dam was to be removed from a nearby golf course, a haul distance of from 300 to 1,300 feet.

## 2.3 Operation

No operational records are available for the Incline Village Lake Dam.

## 2.4 Evaluation

### a. Availability

The availability of engineering data is good and consists of the design drawings and engineering data and information described in Section 2.1, State Geological Maps and U.S.G.S. Quadrangle Sheets. Information was also available on subsurface investigations but no data was available with regard to soil testing or slope stability analysis. Information on design hydrology and hydraulic design was available in the engineering study for the lake and dam.

### b. Adequacy

The drawings from Mr. Bade show the height of the dam above the creekbed as approximately 35 to 40 feet. This compares to a 38 foot field measurement. These drawings also show the total distance between the left abutment and the spillway discharge channel left wall as about 930 feet versus a field measured distance of about 920 feet (Plate 2). Some other small discrepancies between field measurements and the design drawings are as follows: calculations from rough field measurements result in a spillway crest elevation of 510.7 feet above M.S.L. versus an elevation of 513 feet above M.S.L. as quoted by Mr. Bade (the proposed concrete overflow crest is to be 4.5 feet above the existing rock spillway crest); also, the spillway discharge channel was widened from that shown on the plan; a field measured top of dam profile is shown on Plate 2.



The conclusions presented in this report are based on field measurements, the available engineering data, past performance and present condition of the dam. The available data and the field measurements are adequate to evaluate the hydraulic and hydrologic capabilities of the dam in its existing condition.

Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency. These seepage and stability analyses should be performed for appropriate loading conditions (including earthquake loads) and made a matter of record. In the absence of seepage and stability analyses no quantitative evaluation of the structural stability can be made.

c. Validity

Design drawings were available for review. From field measurements, the dam appears to have been constructed according to the available drawings, except for the discrepancies described in Section 1.2a and Section 2.4b.

### SECTION 3: VISUAL INSPECTION

#### 3.1 Findings

##### a. General

A visual inspection of the Incline Village Lake Dam was made on April 23, 1980. The following persons were present during the inspection:

<u>Name</u>	<u>Affiliation</u>	<u>Disciplines</u>
Dr. M.A. Samad	PRC Engineering Consultants, Inc.	Project Engineer, Hydraulics and Hydrology
Mark R. Haynes	PRC Engineering Consultants, Inc.	Soils and Mechanical
Robert G. McLaughlin	PRC Engineering Consultants, Inc.	Civil
Razi Quraishi	PRC Engineering Consultants, Inc.	Geology
John Lauth	Consoer, Townsend & Assoc., Ltd.	Civil and Structural
Larry Bade	Lewis and Associates	Engineer

Specific observations are discussed below.

b. Dam

The top of dam supports an 18 inch thick gravel road. The road is used by large dump trucks to gain access to a rock quarry just downstream of the dam (Photo 1). The depression observed near the right abutment did not seem to be due to settlement or instability of the dam, but appeared to be part of the construction intended profile. No significant deviations in horizontal alignment were apparent. No cracks or settlements were observed. According to Mr. Bade, the dam has never been overtopped and no evidence indicating the contrary was observed.

The upstream slope is protected by limestone riprap from at least the water surface to the top of dam. According to the design drawings, the riprap extends to the heel. The riprap protection from the water surface to the bench and across the bench appears to be adequate protection against wave erosion. The riprap ranged in size from 3-inch to 12-inch cobbles up to 2-foot to 4-foot boulders. No deterioration of the riprap was observed. No wave erosion was observed. The portion of the slope above the bench was protected by a thin layer of riprap. This riprap ranged in size from 3-inches to 6-inches. The surface of the slope appeared to be adequately protected against surface erosion, however, some minor erosion was observed on the slope near the left abutment where the riprap protection was very sparse. Small depressions running down the slope from the top of dam to the bench were observed. The depressions appeared to be caused by the equipment used to place the riprap. Some vegetation was observed growing up through the riprap, mostly on the upper portions of the slope. No depressions, bulges or cracks which would indicate an instability in the embankment were apparent on the slope (Photo 2, 3).

The downstream slope has a sparse vegetative cover. Consequently, erosion due to surface runoff has occurred on the entire slope. Erosion gullies up to 6 inches deep and 12 inches wide were observed. The vegetative cover showed two distinct types of growth. The right half of the dam was covered with green grass and the left half was sparsely covered with dead vegetative growth (Photo 4). The two types of plant growth could be indicative of the two different soil types found on the downstream slope, as described in Section 3.1c. Erosion gullies were observed along the right embankment/abutment contact and at both abutments (Photo 5). The left embankment/abutment contact had the worst erosion and a considerable amount of debris was observed in the area of the erosion (Photo 6). Standing water was observed in a couple of areas just downstream of the mat of riprap at the toe of the dam. The standing water could indicate possible seepage through the embankment and/or foundation (Photo 13). Nevertheless, no measurable seepage was observed. No bulges, depressions or cracks that would indicate an instability in the embankment were apparent on the slope.

Both abutments appeared to be stable and showed no signs of distress. The spillway is cut in behind the right abutment (Photo 6, bottom left & Photo 7). The walls of the spillway are discussed later in Section 3.1 c and d. The access road across the dam crosses both abutments and winds down the right abutment area to the borrow area. No seepage was observed in or around the right abutment. Seepage was observed exiting through a hole approximately 75 feet downstream of the dam adjacent to the left abutment. The flow rate was estimated at approximately 3 to 10 gallons per minute (Photo 14). The seepage did not appear to affect the structural integrity of the embankment or abutment. The discharge was clear. Natural springs are fairly common in the limestone observed on the left abutment.

No rodent activity was observed on the embankment or abutment areas.

c. Project Geology and Soils

(1) Project Geology

The damsite is located on Indian Camp Creek in the Springfield Plateau Section of the Ozark Plateau Physiographic Province. The Springfield Plateau includes that part of the Ozarks that is underlain mainly by rocks of Mississippian age. Most of the Springfield Plateau areas are prairies that are separated by valleys cut 200 to 300 feet below the upland surface. A majority of the area of the Springfield Plateau is overlain by a mantle of chert released by the weathering of the Mississippian limestone. The topography in the damsite vicinity is rolling to hilly, with moderate slopes and U- to V shaped valleys. Elevation ranges from 700 feet above M.S.L. (nearly 1.5 miles southwest of the damsite) to 510 feet above M.S.L. at the Incline Village Lake. The reservoir appears to be water tight and free of any potential slide activity.

The area north and south of the damsite is covered with slope wash deposits of glacial-fluvial and loess in origin consisting of reddish-brown silty clay, with some fine to coarse sand. The inlet and outlet areas of Indian Camp Creek contain Quaternary alluvium.

Outcrops of Mississippian brown to light gray hard sandy Limestone (Burlington Formation) and light gray Dolomite are exposed at the right and left abutments (Photo 15, 16). Limestone and Dolomite beds are horizontally bedded. A localized undulating structure in the limestone beds was observed at the upstream cut of the left abutment. This may

be attributed to the differential compaction rather than tectonic forces. The areal bedrock geology beneath the glacial fluvial slope wash deposits, as shown on the Geologic Map of Missouri (1979), Plate 5, consists of Mississippian Keokuk-Burlington Limestone, Ordovician Kimmswick Limestone interbedded with Cherty Dolomite and Green Shale.

No faults have been identified in the vicinity of the damsite. The closest trace of a fault to the damsite is the Cap Au Gres Faulted Flexure nearly 20 miles north of the site. This faulted flexure had its last movement in Post Pennsylvanian, Pre-Pleistocene time and appears to have no effect on the dam.

Incline Village Lake Dam consists of a zoned earth embankment. A rock cut principal spillway in the Burlington Limestone is located at the right end of the embankment, and a low-level outlet pipe is located at the central section of the embankment. Based on available data and visual inspection, the embankment is assumed to rest on Burlington Limestone with a core trench excavated into the bedrock. The foundation material underlying the low-level outlet pipe consists of compacted embankment fill. (Brown fine to medium silty sand to reddish-brown silty clay).

The spillway rock cut slopes are relatively stable. Minor localized rock debris were observed at the foot of the slope at the walls of the spillway discharge channel.

## (2) Project Soils

According to the "Missouri General Soil Map and Soil Association Descriptions" published by the Soil Conservation Service, the materials in the general area of the dam belong to the soil series of Hatton-Keswick-Lindley-Goss in the Central Mississippi Valley Wooded Slopes family. The soils were basically formed from loess, glacial till and cherty limestone. The permeability of these soils ranges from moderate to very slow. The Lindley soil is generally quite susceptible to erosion. If the Lindley soil type was used in the embankment, the potential of failure of the embankment would be increased due to erosion during overtopping.

Materials were removed from the downstream slope in two locations. One location was approximately two hundred feet to the left of the right abutment contact and the other location was near the low level outlets. Both samples were removed from the embankment at approximately 18 inches below the vegetative cover. The material removed from the embankment near the right abutment appeared to be a brown, silty fine to medium sand with traces of fine to coarse limestone gravel. Based upon the Unified Soil Classification System, the soil would probably be classified as a SM. This soil type generally has the following characteristics: semipervious to impervious with a coefficient of permeability less than 100 feet per year, medium to high shear strength, and a low to intermediate resistance to piping. The material removed from the embankment near the low level outlets appeared to be a reddish brown silty clay with a trace of fine to coarse sand. Based upon the Unified Soil Classification System, the soil would probably be classified as a CL. This soil type generally has the following characteristics: impervious with a coefficient of permeability less than 1.0 foot per year,

medium shear strength, and a high resistance to piping. Approximately the left half of the downstream slope appeared to be the SM material and the right half of the slope the CL material.

Materials removed from below the riprap on the upper portion of the upstream slope appeared to be approximately the same as the SM material described above.

d. Appurtenant Structures

(1) Spillway

The spillway presently has a vertical, rough cut, rock face approximately 14 feet high with an uneven crest; this causes the flow under normal conditions to spill only at the left side where the crest is lowest in elevation (Photo 7). Since the spillway was blasted, there are cracks, fissures, loose rock etc. which may cause problems in the future. However, according to Mr. Bade a rectangular weir will be constructed this year, and fractures will be filled with grout as a part of the construction of this weir; the weir will be set back 15 feet from the edge and will spill water at the one elevation of 517.5 feet above M.S.L. Debris seems to be collecting in the wide open pool area just downstream from the crest (Photo 8). From all appearances during the inspection the spillway area was entirely adequate and no problems needing immediate attention were noticed.



## (2) Outlet Works

Reportedly, there are two low level drain pipes with separate gate valve controls provided for the dam; however, only one gate valve was observed on the day of the inspection. A stack of hay bales was observed to the right of the gate valve which was observed. It is assumed that the hay bales were covering the second gate valve and that the bales were placed there to protect the valve from freezing during the winter (Photo 11). The hay bales were moist and some standing water was observed near the base of the stack. It appears that the gate valve is leaking. Both valves are reportedly operable and were operated last winter in order to drain the reservoir; this was done so that work could be performed in the reservoir. The valves were not operated on the day of the inspection. Leakage was observed between the gate and gate seat and around the stem of the observed gate. No seepage was observed around the pipe. The discharge channel for the drain appears to be adequately protected by riprap (Photo 12). The inlets of the two drains were not observed due to the reservoir level.

### e. Reservoir Area

The water surface elevation was approximately 511 feet above M.S.L. on the day of the inspection. The reservoir rim is sloped gently and there were no indications of instability or severe erosion observed. The slopes above the rim are grass covered until the forest lands begin. It is in these grass covered areas where dwellings and buildings have been built (they are approximately 500 feet from the rim and sit 15 to 20 feet above the rim.); other regions are tree covered immediately adjacent to the shore line (Photo 7). The entire shoreline of over 8 miles was not inspected.

f. Downstream Channel

The downstream channel is well defined. It was clear of debris and vegetation. Some trees were observed growing on the sides. The channel is approximately 20 feet wide and has a side slope of 1V to 1H on both sides. The channel is approximately 3 feet deep below the damsite.

3.2 Evaluation

The visual inspection did not reveal any items which are sufficiently significant to indicate a need for immediate remedial action. The following conditions were observed which could affect the safety of the dam or which will require maintenance within a reasonable period of time.

1. The erosion on the upstream slope, the downstream slope, and the abutment/embankment contacts does not appear to affect the structural stability of the dam in its present condition (Photo 5,6).

2. The possible seepage indicated by the standing water observed downstream of the toe does not affect the structural stability of the dam in its present condition. Nevertheless, if the rate of seepage were to increase, it is possible that the seepage could transport soil particles which could cause piping of embankment material which could lead to the eventual failure of the embankment (Photo 13).

3. The vegetation on the upstream slope does not have an adverse effect on the dam in its present condition. Nevertheless, it would be fairly difficult to maintain the vegetation properly with the riprap protection on the slope. A heavy vegetative growth on the slope could prevent a comprehensive inspection

of the slope and potential problems could go undetected (Photo 2,3).

4. The fractures and cracking in the face and crest of the spillway could conceivably get progressively worse due to freeze-thaw cycles in future years if left in "as is" condition. This condition could easily be remedied at the time of the construction of the weir.

5. The leakage observed through the gate valve of the low level drain does not affect the normal operation of the valve or the safety of the dam. Nevertheless, the leakage should be properly repaired for continual leakage can only worsen the condition (Photo 11).

## SECTION 4: OPERATIONAL PROCEDURES

### 4.1 Procedures

There are no specific procedures which are followed for the operation of Incline Village Lake Dam. The water level below the spillway crest is allowed to remain as high as possible.

### 4.2 Maintenance of Dam

The dam is maintained by Incline Village Investment Inc. The downstream and upstream slopes, along with the top of dam, are kept free of saplings and brush. The northern one-half of the downstream slope does not have an adequate grass cover and numerous erosion gullies have formed on the slope. Fill material had recently been added to the top of dam at the left abutment due to erosion in this area.

### 4.3 Maintenance of Operating Facilities

Two 22-inch diameter drain lines are provided in the dam. A 24-inch diameter gate valve is installed on the downstream end of each drain line. The two valves are adjacent to each other.

One 24-inch diameter drain valve is located in a straw pile for freezing protection. According to Mr. Larry Bade, this drain valve has a crack in the upper portion of the valve between the main body and the stem. The crack causes a minor leak with a slow drip. According to Mr. Larry Bade, the valve is operable and it was last opened about a year ago.

The exposed 24-inch diameter gate valve was leaking during the dam inspection (Photo 11). The valve is operable and it was last opened in March, 1980.

4.4      Description of Any Warning System in Effect

The inspection team is not aware of any existing warning system for this dam.

4.5      Evaluation

It would appear that attempts are being made to maintain the dam and its surrounding reservoir area. The low level outlet drain valves should be inspected periodically to check their ease of operation.

## SECTION 5: HYDRAULIC/HYDROLOGIC

### 5.1 Evaluation of Features

#### a. Design

The watershed area of the Incline Village Lake Dam measured from the U.S.G.S. Foristell and Wright City, Missouri, Quadrangle sheets consists of approximately 27 square miles. However, according to the available design data, the drainage area is about 24 square miles. The watershed area is mostly forested with some pasture and agricultural land. Land gradients in the watershed average roughly 1/2 percent. The Incline Village Lake Dam is located on Indian Camp Creek. At its longest arm the watershed is approximately 9 miles long. A drainage map showing the watershed is presented in Plate 1 in Appendix B.

Evaluation of the hydraulic and hydrologic features of Incline Village Lake Dam was based upon criteria set forth in the Corps of Engineers' "Engineer Regulation No. 1110-2-106" and additional guidance provided by the St. Louis District of the Corps of Engineers. The Probable Maximum Flood (PMF) was calculated from the Probable Maximum Precipitation (PMP) using the methods outlined in the U.S. Weather Bureau Publication, Hydrometeorological Report No. 33. The probable maximum storm duration was set at 24 hours, and storm rainfall distribution was based upon criteria given in the Corps of Engineers' EM 1110-2-1411 (Standard Project Storm). The Soil Conservation Service (SCS) method was used for deriving the unit hydrograph, utilizing the Corps of Engineers' computer program HEC-1 (Dam Safety Version). The unit hydrograph

parameters are presented in Appendix B. The SCS method also was used for determining the loss rate. The hydrologic soil group of the watershed was determined by use of published soil maps. The hydrologic soil group of the watershed and the SCS curve number are presented in Appendix B. The curve number, unit hydrograph parameters, the PMP index rainfall and the percentages for various durations were directly input to the HFC-1 (Dam Safety Version) computer program to obtain the PMF hydrograph. The computed peak inflows of the PMF and one-half of the PMF are 74,822 cfs and 37,411 cfs, respectively.

Both the PMF and one-half of the PMF inflow hydrographs were routed through the reservoir by the Modified Puls Method also utilizing the HFC-1 (Dam Safety Version) computer program. A storm of 50 percent and 25 percent PMF, respectively, preceded the PMF and 50 percent PMF by four days. The reservoir was assumed at the mean annual high water level at the beginning of the antecedent storm. The mean annual high water level for Incline Village Lake was estimated to be at the crest of the spillway. The antecedent 50 percent PMF storm, when routed through the reservoir, leaves the reservoir at approximately the same elevation as the crest of the spillway at the end of the four day period. Thus, the reservoir was assumed at the spillway crest at the start of the routing computation for the PMF, one-half of the PMF and other PMF ratio floods. The peak outflow discharges for the PMF and one-half of the PMF are 72,040 and 35,810 cfs, respectively. Only the PMF when routed through the reservoir resulted in overtopping of the dam.

The size of physical features utilized to develop the stage-outflow relation for the spillway and overtopping of the dam were prepared from field notes and sketches prepared during the field inspection. The reservoir elevation-area

data were obtained from the U.S.G.S. Foristell and Wright City, Missouri Quadrangle topographic maps (7.5 minute series). The spillway and dam overtop-rating curve and the reservoir-elevation-area curve are presented as Plates 2 & 3, respectively, in Appendix B.

From the standpoint of dam safety, the hydrologic design of a dam must aim at avoiding overtopping. Overtopping is especially dangerous for an earth dam because of its erodable characteristics. The safe hydrologic design of an embankment dam requires a spillway discharge capability combined with an embankment crest height that can handle a very large and exceedingly rare flood without overtopping.

The Corps of Engineers designs dams to safely pass the Probable Maximum Flood that could be generated from the dam's watershed. This is generally the accepted criterion for major dams throughout the world and is the standard for dam safety where overtopping would pose any threat to human life. Accordingly, the hydrologic requirement for safety for this dam is the capability to pass the Probable Maximum Flood without overtopping.

b. Experience Data

It is believed that records of reservoir stage or spillway discharge are not maintained for this site. However, according to Mr. Bade, the design and construction engineer for the dam, the maximum reservoir level was at El 521 in 1978.



c. Visual Observations

Observations made of the spillway during the visual inspection are discussed in Section 3.1.d(1) and evaluated in Section 3.2.

d. Overtopping Potential

As indicated in Section 3.1.a, only the Probable Maximum Flood, when routed through the reservoir, resulted in overtopping of the dam. The peak outflow discharges for the PMF and one-half of the PMF are 72,040 and 35,810 cfs, respectively. The maximum capacity of the spillway just before overtopping the dam is 43,724 cfs. The PMF overtopped the dam by 5.02 feet. The total duration of flow over the top of dam was 4.5 hours. The spillway/reservoir system of Incline Village Lake Dam is capable of accommodating a flood equal to approximately 60 percent of the PMF just before overtopping the dam.

Incline Village Lake Dam is still under construction. According to the available design data, the reservoir/spillway system of Incline Village Lake Dam in its final shape is designed to accommodate the 50-year storm flood. Based on our evaluation, the reservoir/spillway system of Incline Village Lake Dam in its present state can accommodate the one-percent chance flood without overtopping the dam.

The surface soils in the embankment appear to vary from silty clay to silty sand. The dam is overtopped by over five feet during the occurrence of the PMF. The spillway being a rock-cut channel, should be able to withstand high velocity of flow during the PMF without being subject to excessive erosion; however, the downstream slope of the dam

might be eroded and thus endanger the safety of the dam due to overtopping during the occurrence of the PMF.

The failure of the dam could cause extensive damage to the property downstream of the dam and possible loss of life. The estimated damage zone extends approximately six miles downstream of the dam. Within the damage zone are three dwellings, a U.S. highway (Hwy. 61), and a light duty road and bridge.

## SECTION 6: STRUCTURAL STABILITY

### 6.1 Evaluation of Structural Stability

#### a. Visual Observations

There were no major signs of settlement or distress observed on the embankment or foundation during the visual inspection. The upstream slope of the embankment appears to be adequately protected from wave erosion by riprap. The surface erosion on the upstream slope, the downstream slope, and the abutment/embankment contacts could affect the stability of the dam if allowed to continue. The possible seepage observed downstream of the toe does not appear to affect the stability of the dam in its present condition. However, this condition could worsen and eventually severely affect the stability of the dam. In the absence of seepage and stability analyses, no quantitative evaluation of the structural stability can be made.

The spillway crest and the adjacent pool area (which was mostly empty) are hewn out of rock and exhibit no observable signs of structural instability. It seems plausible that a certain amount of rock will break loose from the blasted faces for some time to come (Photo 7).

The low level drain did not exhibit signs of structural instability.

b. Design and Construction Data

Design computations pertaining to the embankment were not uncovered during the report preparation phase. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available. No embankment or foundation soil parameters were available for carrying out a conventional stability analysis on the embankment. No construction data or specifications relating to the degree of embankment compaction were available for use in a stability analysis.

c. Operating Records

No operating records are available relating to the stability of the dam or appurtenant structures. The water level on the day of inspection was slightly above the crest of the spillway at one point, and it is assumed that the reservoir remains close to full at all times. The low level drain is reportedly operable.

d. Post Construction Changes

No post construction changes to the embankment exist which will affect the structural stability of the dam. A modification which has been completed since the dam was constructed, is the spillway discharge channel widening to 100 feet and the spillway crest lengthening to approximately 250 feet. The depth of the channel was also increased. Other changes occurred within the reservoir; these involved lowering of the reservoir on two different occasions in order to deepen cove areas and to remove driftwood.

Mr. Bade indicated that there are plans for further modifications to the spillway structure. A weir wall is going to be built around the semi-circular perimeter of the existing spillway inlet. The wall will be approximately 250 to 260 feet long and the elevation of the top of the wall will be 517.50. This will raise the normal pool elevation of the lake to approximately 517.50. Grout will also be injected into the rock at the northern third of the existing spillway inlet. This rock was fractured during the widening of the spillway.

e. Seismic Stability

The dam is located in Seismic Zone 2, as defined in "Recommended Guidelines For Safety Inspection of Dams" as prepared by the Corps of Engineers, and will not require a seismic stability analysis. An earthquake of the magnitude which would be expected in a Seismic Zone 2 should not cause distress to a well designed and constructed earth dam. Available literature indicates no active faults exist near the vicinity of the damsite.

## SECTION 7: ASSESSMENT/REMEDIAL MEASURES

### 7.1 Dam Assessment

The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation, however, the investigation is intended to identify any need for such studies.

It should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team.

It is also important to note that the condition of a dam depends upon numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be assurance that an unsafe condition could be detected.

#### a. Safety

The spillway capacity of Incline Village Lake Dam is found to be "Inadequate". The spillway/reservoir system will accommodate about 60 percent of the PMF without overtopping. The surface soils in the embankment appears to vary from silty clay to silty sand. The dam is overtopped by over five feet during the occurrence of the PMF. The spillway, being a rock cut channel, should be able to withstand high

velocity flow during the PMF without being subject to excessive erosion; however, the downstream slope of the dam might be eroded and thus endanger the safety of the dam due to overtopping during the occurrence of the PMF.

No quantitative evaluation of the safety of the embankment can be made in view of the absence of seepage and stability analyses. The present embankment, however, has reportedly performed satisfactorily since its construction without failure or evidence of instability. The dam has reportedly never been overtopped.

The safety of the dam can be improved if the deficiencies described in Section 3.2 and 6.1a are properly corrected as described in Section 7.2b.

b. Adequacy of Information

Pertinent information relating to the design and construction of the dam consisted of two design drawings and other items as listed in Section 2.1. The conclusions presented in this report are based on field measurement, past performance and present condition of the dam. Information on the design hydrology and hydraulic design of the dam were available. However, this information was of no significant value in Phase I inspection and evaluation of the dam. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency.

c. Urgency

The remedial measures recommended in Paragraph 7.2 should be accomplished within a reasonable period of time. The item recommended in Paragraph 7.2a should be pursued on a high priority basis.

d. Necessity for Phase II Inspection

A Phase II inspection is not felt to be necessary, based on results of the Phase I inspection. However, the remedial remedial measures recommended in Paragraph 7.2 should be undertaken within a reasonable amount of time.

7.2 Remedial Measures

a. Alternatives

There are several general options that may be considered to reduce the possibility of dam failure or to diminish the harmful consequences of such a failure. Some of these options are:

1. Increase the spillway capacity to pass the Probable Maximum Flood without overtopping the dam.
2. Increase the height of the dam enough to pass the PMF without overtopping the dam. An investigation should also be done that includes studying the effects on the structural stability of the existing embankment. The overtopping depth during the occurrence of the PMF, stated in Section 5.1d, is not the required or recommended increase in the height of the dam.




3. A combination of 1 and 2 above.

b. O & M Procedures

1. The possible seepage observed just downstream of the riprap mat at the toe of the dam should be monitored to detect any changes in turbidity, location, or quantity. Any changes should be reported and investigated further (Photo 13).
2. The erosion on the upstream slope, the downstream slope, and the embankment/abutment contacts should be properly repaired by backfilling the damaged areas with suitable material and an adequate compaction achieved. Then, the damaged areas and the entire downstream slope should be adequately protected from surface erosion to prevent further deterioration. Debris should be cleared away (Photo 5,6).
3. The vegetation on the upstream slope should be removed and prevented from continuous extensive growth (Photo 2,3).
4. Major cracks and fractures in the spillway crest should be filled properly with a suitable mix of mortar, and the vertical spillway face should be examined for looseness or other type problem areas and firmed up as much as is reasonably possible (Photo 7). Also, the loose brush and debris within the spillway area just downstream from the crest wall should be cleared away (Photo 8).


5. The leakage observed through one of the valves of the low level drain should be properly repaired since continual leakage can only worsen the condition (Photo 11). The valves should be properly maintained as recommended by the valve manufacturer and the valves operated periodically.
6. Seepage and stability analyses should be performed by a professional engineer experienced in the design and construction of earth dams.
7. The owner should initiate the following programs:
  - (a) Periodic inspection of the dam by a professional engineer experienced in the design and construction of earthen dams.
  - (b) Set up a maintenance schedule and log all visits to the dam for operation, repairs and maintenance.

PLATES



LOCATION MAP - INCLINE VILLAGE LAKE DAM

MO. 11041



INCLINE VILLAGE LAKE DAM (MO. 11041)  
PLAN AND SECTIONS


LAKE

WARREN COUNTY  
ST. CHARLES COUNTY

SPILLWAY

DIVERT CATCH CHANNEL

PAGE 24 18



NORTH  
SCALE 1:50'

Centerline of


L A K E

27/11/18

PLATE 1. BINGO, PLAIN AND PARCHMENT, AND OTHER  
OF THE MEXICAN CIVILIZATION


161






LAKE

LEWIS AND ASSOCIATES	
101 EAST WALTON	
WARRENTON, MISSOURI 63383	
THE ALBANY VILLAGE	
ALBANY, MISSOURI	
DATE	NOV 11 1977
BY	DR. B. J. L.
CHECKED BY	DR. B. J. L.





⊕ LOCATION OF DAM

NOTE: LEGEND OF THIS DAM IS ON PLATE 6.


#### REFERENCE

GEOLOGIC MAP OF MISSOURI  
DEPARTMENT OF NATURAL RESOURCES  
MISSOURI GEOLOGICAL SURVEY  
KENNETH H. ANDERSON, 1979

REGIONAL GEOLOGICAL MAP  
OF  
INCLINE VILLAGE LAKE DAM

LEGEND

<u>PERIOD</u>	<u>SYMBOL</u>	<u>DESCRIPTION</u>
QUATERNARY	Qal	ALLUVIUM SAND, S LT. GRAVEL
PENNSYLVANIAN	{ Pm	MARMATON GROUP CYCLIC DEPOSITS OF SHALE, LIMESTONE AND SANDSTONE
	{ Pcc	CHEROKEE GROUP CYCLIC DEPOSITS OF SHALE, LIMESTONE AND SANDSTONE
MISSISSIPPIAN	{ Mm	ST LOUIS FORMATION LIMESTONE INTERBEDDED WITH SHALE
	{ Mm	SALEM FORMATION LIMESTONE INTERBEDDED WITH SHALE AND SILTSTONE
	{ Mm	WARSAW FORMATION ARGILLACEOUS LIMESTONE AND CALCAREOUS SHALE
	{ Mo	KEOKUK - BURLINGTON FORMATION CHERTY GRAYISH BROWN SANDY LIMESTONE
	{ Mk	NORTHVIEW - COMPTON AND BACHELOR FORMATION
DEVONIAN	D	CHATTANOOGA SHALE, SYLAMORE SANDSTONE
ORDOVICIAN	{ Ou	CINCINNATIAN SERIES, SHALE, LIMESTONE AND DOLOMITE
	{ Omk	MAQUOKETA SHALE KIMMSWICK LIMESTONE
	{ Odp	DECORAH FORMATION GREEN TO GRAY CALCAREOUS SHALE WITH THIN FOSSILIFEROUS LIMESTONE



APPENDIX A

PHOTOGRAPHS




PHOTO INDEX  
FOR  
INCLINE VILLAGE LAKE DAM

Incline Village Lake Dam  
Photographs

- Photo 1 - Top of dam showing 8" to 10" thickness of gravel roadway and excavated area of cliff wall of spillway at right side.
  
- Photo 2 - Upstream slope of dam showing rock protection and 10-foot berm at the water edge. (Looking left.)
  
- Photo 3 - Upstream slope of dam showing rock protection and 10-foot berm at water edge. (Looking right.)
  
- Photo 4 - Overview of downstream slope of dam showing partial green grass cover and partial dead vegetative cover. Also, shows gravelled area downstream of toe.
  
- Photo 5 - View of deep gully along right abutment downstream contact area.
  
- Photo 6 - Left downstream abutment contact area showing logs, brush, and eroding area.
  
- Photo 7 - Principal spillway showing pool area, lake, and surrounding area of reservoir rim.
  
- Photo 8 - Downstream area of spillway showing large discharge channel with brush and logs.
  
- Photo 9 - View of channel along toe of dam showing construction road crossing, bank erosion, and gravel cover at toe of slope.
  
- Photo 10 - Downstream channel showing relatively wide tree-lined waterway.

- Photo 11 - Low-level outlets at toe of dam showing one valve badly leaking and the condition of the adjacent valve covered by straw.
- Photo 12 - Valve outlet channel to downstream channel.
- Photo 13 - View of possible seepage from under gravel cover at toe of dam.
- Photo 14 - View of spring off of dam embankment, but within 20 feet of left downstream abutment of contact.
- Photo 15 - Outcrops of Mississippian brown to light grey, hard, sandy limestone (Burlington Formation) and light grey Dolomite.
- Photo 16 - Same as Photo 15, different area; shows also, undulation.



Incline Village Lake Dam



Photo 1



Photo 2

Incline Village Lake Dam



Photo 3



Photo 4

Incline Village Lake Dam




Photo 5



Photo 6

Incline Village Lake Dam



Photo 7



Photo 8

Incline Village Lake Dam



Photo 9



Photo 10

Incline Village Lake Dam



Photo 11




Photo 12

Incline Village Lake Dam



Photo 13



Photo 14

Incline Village Lake Dam



Photo 15




Photo 16



APPENDIX B

HYDROLOGIC AND HYDRAULIC COMPUTATIONS






INCLINE VILLAGE LAKE DAM MO 11041

DRAINAGE BASIN

DRAINAGE BOUNDARY ---

12



INCLINE VILLAGE LAKE DAM (MO. 11041)  
DOWNSTREAM HAZARD ZONE

ECI-4

# PRC ENGINEERING CONSULTANTS, INC.

DAM SAFETY INSPECTION / MISSOURI


SHEET NO 1 OF 5

INCLINE VILLAGE DAM

# 11041

JOB NO. 1263

BY FZ DATE JUNE 2, 1968



DAM SAFETY / MISSOURI

JOB NO. 1263

INCLINE VILLAGE

#11041

BY FZ DATE JUNE 80

- ① Spillway = assumed critical depth over 246 feet Crest.  
because of a 14' drop.

$$V_1 = \sqrt{y_c g}$$

$$Q_1 = 246 \sqrt{y_c^3 g} \quad \frac{V_1^2}{2g} = \frac{y_c}{2} \quad H_1 = \frac{3}{2} y_c$$

②  $H_2 = H_1 - 17.5$

$$Q_2 = C_2 L_2 H_2^{1.5} \quad L_2 = 42$$

③  $H_3 = H_1 - 14.9$

$$y_{c3} \leq 2.6 \Rightarrow y_{c3} = \frac{4}{3} H_3 \quad T_3 = \frac{22}{2.6} y_{c3} \quad A = \frac{T_3 y_{c3}}{2}$$

$$Q_3 = \sqrt{\frac{A^3 g}{T_3}} = 17.04 y_{c3}^{5/2}$$

$$y_{c3} > 2.6$$

$$y_{c3} = \frac{2}{3} \left( H_3 + \frac{2.6}{4} \right) = \frac{2}{3} (H_3 + 0.65)$$

$$T_3 = 22' \quad A_3 = 22(y_{c3} - 1.3)$$

$$Q_3 = \sqrt{\frac{A^3 g}{T_3}} = 22 \sqrt{(y_{c3} - 1.3)^3 g}$$

④  $H_4 = H_3$

$$y_{c4} \leq 1.8$$

$$y_{c4} = \frac{4}{3} H_3 \quad T_4 = \frac{33}{1.8} y_{c4} \quad A_4 = \frac{T_4 y_{c4}}{2}$$

$$Q_4 = \sqrt{\frac{A^3 g}{T_4}} = 36.8 y_{c4}^{5/2}$$

$$y_{c4} > 1.8$$

$$y_{c4} = \frac{2}{3} \left( H_4 + \frac{1.8}{4} \right) = \frac{2}{3} (H_3 + 0.45)$$

$$T_4 = 33 \quad A_4 = 33(y_{c4} - 0.9)$$

$$Q_4 = \sqrt{\frac{A^3 g}{T_4}} = 33 \sqrt{(y_{c4} - 0.9)^3 g}$$

DAM SAFETY / MISSOURI

SHEET NO. 3 OF 5

INCLINE VILLAGE # 11041

JOB NO. 1263

BY FZ DATE JUNE 80

$$\textcircled{5} \quad H_5 = H_1 - 16.7 \quad y_{c5} \leq 1.5 \Rightarrow y_{c5} = \frac{4H_5}{3} \quad T_5 = \frac{95}{1.5} y_{c5} \quad A_5 = \frac{T_5 y_{c5}}{2}$$

$$Q_5 = \sqrt{\frac{A_5^3 g}{T_5}} = 127.1 y_{c5}^{5/2} \quad \textcircled{1}$$

$$y_{c5} > 1.5 \Rightarrow y_{c5} = \frac{2}{3} (H_5 + 0.375) \quad T_5 = 95 \quad \textcircled{1}$$

$$A_5 = 95 (y_{c5} - 0.75) \quad \textcircled{1}$$

$$Q_5 = \sqrt{\frac{A_5^3 g}{T_5}} = 95 \sqrt{(y_{c5} - 0.75)^3 g}$$

$$\textcircled{6} \quad H_6 = H_1 - 18.2 \quad y_{c6} \leq 1.1 \quad y_{c6} = \frac{4}{3} H_6 \quad T_6 = \frac{158}{1.1} y_{c6} \quad A_6 = \frac{T_6 y_{c6}}{2}$$

$$Q_6 = \sqrt{\frac{A_6^3 g}{T_6}} = 288.2 y_{c6}^{5/2}$$

$$y_{c6} > 1.1 \quad y_{c6} = \frac{2}{3} (H_6 + 0.275) \quad T_6 = 158$$

$$A_6 = 158 (y_{c6} - 0.55)$$

$$Q_6 = 158 \sqrt{(y_{c6} - 0.55)^3 g}$$

$$\textcircled{7} \quad H_7 = H_1 - 19.3 \quad Q_7 = C_7 L_7 H_7^{3/2} \quad L_7 = 570$$

## PRC ENGINEERING CONSULTANTS, INC.

PAM SAFETY MISSOURI

SHEET NO. 4 OF 5

INCLINE VILLAGE # 11041

JOB NO. 1263

BY FLZ DATE JUNE 80

①				②		③		④		Q
Yc	V <sub>i</sub>	H <sub>i</sub>	WSEL	H <sub>2</sub>	C <sub>2</sub>	Q <sub>2</sub>	H <sub>3</sub>	Yc <sub>3</sub>	Q <sub>3</sub>	
0	0	0	H <sub>i</sub> +510.7							Subtotal.
2	8.0	3.0	510.7							0
4	11.5	6.0	513.7							3948
6	13.9	9.0	516.7							11 167
8	16.0	12.0	519.7							20 516
10	17.9	15.0	522.7							31 586
11	18.8	16.5	525.7				0.1	0.08	0.	44 143
12	19.7	18.0	527.2	0.5	3.02	4.5	1.6	1.28	32	51 027
12.4	20.0	18.6	528.7	1.1	3.035	147	3.1	2.48	165	58 571
12.8	20.3	19.2	529.3	1.7	3.045	284	3.7	2.90	253	61 831
13.0	20.5	19.5	529.9	2.0	3.045	362	4.3	3.30	353	65 202
13.2	20.6	19.8	530.2	2.3	3.05	447	4.6	3.50	407	66 924
13.4	20.8	20.1	530.5	2.6	3.05	537	4.9	3.70	464	68 672
13.6	20.9	20.4	530.8	2.9	3.05	633	5.2	3.90	523	70 442
14	21.2	21.0	531.1	3.5	3.05	839	5.5	4.10	585	72 236
15	22.0	22.5	531.7	5.0	3.05	1432	6.1	4.50	715	75 886
			533.2				7.6	5.50	1075	85 371



ECI-4

## PRC ENGINEERING CONSULTANTS, INC.

DAM SAFETY / MISSOURI

SHEET NO. 5 OF 5


INCLINE VILLAGE

# 11041

JOB NO. 1663

BY FZ DATE JUNE 80

WSEL	Q	(5)			(6)			(7)			Q
		H <sub>5</sub>	Y <sub>05</sub>	Q <sub>5</sub>	H <sub>6</sub>	Y <sub>06</sub>	Q <sub>6</sub>	H <sub>7</sub>	C <sub>7</sub>	Q <sub>7</sub>	
	H <sub>1</sub>	Subtotal									TOTAL
510.7	0	0									0
513.7	3.0	3948									3948
516.7	6.0	11167									11167
519.7	9.0	20516									20516
522.7	12.0	31586									31586
525.7	15.0	44143									44143
527.2	16.5	51027									51027
528.7	18.0	58571	1.3	140							58711
529.3	18.6	61831	1.9	362	0.4	0.32	17				62210
529.9	19.2	65202	2.5	679	1.0	0.80	165				66046
530.2	19.5	66924	2.8	861	1.3	1.04	318	0.2	2.97	151	68254
530.5	19.8	68672	3.1	1057	1.6	1.25	525	0.5	3.02	609	70863
530.8	20.1	70442	3.4	1266	1.9	1.45	766	0.8	3.03	1236	73710
531.1	20.4	72236	3.7	1487	2.2	1.65	1034	1.1	3.035	1996	76752
531.7	21.0	75886	4.3	1963	2.8	2.05	1647	1.7	3.045	3847	83343
533.2	22.5	85371	5.8	3330	4.3	3.05	3544	3.2	3.05	9952	102197



INCLINE VILLAGE LAKE DAM (MO. 11041)  
SPILLWAY & OVERTOP RATING CURVE

## PRC ENGINEERING CONSULTANTS, INC.

DAM SAFETY INSPECTION - MISSOURI

SHEET NO. 1 OF 1

DAM NAME: Incline Village


ID NO.: 11041

JOB NO. 1263

RESERVOIR ELEVATION - AREA DATA

BY J.E.K.  
#2DATE 4/21/80  
JUNE 80

ELEV. (M.S.L.) (Ft.)	RESERVOIR SURFACE AREA (Acres)	REMARKS
486	0	Assumed bottom of lake.
500	24	Measured on USGS Map
510.7	90	Interpolated - Crest of Emergency Spillway
520	173	Measured on USGS Map
530	320	Interpolated - Top of dam.
540	515	Measured on USGS Map
550	745	Interpolated
560	1000	Measured on USGS Map



B-II INCLINE VILLAGE LAKE DAM (MO. 11041)  
RESERVOIR AREA CURVE

DAM SAFETY INSPECTION / MISSOURI

SHEET NO. 3 OF

DAM NAME: INCLINE VILLAGE #11041

JOB NO. 1263

PROBABLE MAXIMUM PRECIPITATION

BY F2 DATE June 80

DETERMINATION OF PMP

1) Determine drainage area of the basin

D.A. = 27 sq miles.

2) Determine PMP Index Rainfall (for D.A. = 200 sq. mi. &amp; 24 hr. duration)

Location of centroid of basin,


Long. =  $91^{\circ}02'$ Lat. =  $38^{\circ}50'$ 

PMP = 25" (from Fig. 1, HMR 33)

Zone = 7

3) Determine basin rainfall in terms of percentage of PMP Index  
Rainfall for various durations.  
(from Fig. 2, HMR 33)

Duration (Hrs.)	Percent of Index Rainfall (%)	Total Rainfall (Inches)	Rainfall Increments (Inches)	Duration of Increment (Hrs.)
6	99	22.5	22.5	6
12	108	27.0	4.5	6
24	118	29.5	2.5	12
48	128	32.0	2.5	24



⊕ Location of Basin Centroid

Incline Village Lake Dam

CMO 1134











FIGURE 2  
SEASONAL VARIATION  
DEPTH-AREA-DURATION RELATIONSHIPS  
Percentage to be applied to 200 square miles  
24 hour probable maximum precipitation values  
for THE-ALL-SEASON ENVELOPE



DAM SAFETY INSPECTION/MISSOURI-1980 SHEET NO. 1 OF 1  
 INCLINE VILLAGE LAKE DAM JOB NO. 1222  
 UNIT HYDROGRAPH PARAMETERS BY JAH DATE 9/11/80

- 1) Drainage Area,  $A = 27.0 \text{ sq. mi.}$
- 2) Length of Longest Stream,  $L = 60,100' = 11.38 \text{ Miles}$
- 3) Elevation of Streambed at 0.65L,  $E_{0.65} = 735$
- 4) Elevation of Streambed at 0.10L,  $E_{0.10} = 522$
- 5) Slope of Stream,  $S = (E_{0.65} - E_{0.10}) / 0.75L \approx 5\%$
- 6) Time of Concentration,  $T_c$ :

By Velocity Estimate Guide

Slope = 5%  $\Rightarrow$  Avg. Velocity,  $V = 4 \text{ fps.}$

$$T_c = L/V = (60,100/4)/3600 = 4.17 \text{ hrs.}$$

- 7) Lag Time,  $T_L = 0.6 T_c = 2.50 \text{ hrs.}$
- 8) Unit Duration,  $D = T_c/3 = 0.83 \text{ hr.}$   
 Use  $D = 0.5 \text{ hr.}$
- 9) Time to Peak,  $T_p = D/2 + T_c = 2.75 \text{ hrs.}$

- 10) Peak Discharge,  $q_p$ :

$$q_p = (484 \times A^{0.78}) / T_p = \frac{484 \times 27}{2.75} = \underline{\underline{4752 \text{ cfs}}}$$



## PRC ENGINEERING CONSULTANTS, INC.

DAM SAFETY INSPECTION / MISSOURI - 1980 SHEET NO. 4 OF         
 DAM NAME: INCLINE VILLAGE #11041 JOB NO. 1263  
 CURVE NUMBER DETERMINATION BY FR DATE JUNE 80

I) SOIL GROUP

WATERSHED SOILS IN THE BASIN CONSIST OF GROUP A.

Most of it is Hutton, Keswick, Lindley, Goss

A.  
B.  
C.  
D.

GROUP C SOILS SEEM TO PREDOMINATE THE BASIN. THEREFORE,  
 ASSUME GROUP C SOILS FOR THE ENTIRE WATERSHED  
 FOR HYDROLOGIC PURPOSES.

II) COVER COMPLEX

ASSUMED LAND USE	ASSUMED HYDROLOGIC CONDITION	PER CENT AREA	CN (AMC II)
FOREST	FAIR	60%	77
PASTURE	FAIR	20%	86
ROW CROPS	POOR	20%	88

III) CURVE NUMBER

WEIGHTED AVERAGE CN = 81 FOR AMC II

CURVE NUMBER = 92 FOR AMC III

HEC1DB INPUT DATA



INFLOW PMF AND ONE-HALF PMF HYDROGRAPHS

EXAMPLE OF SCHEMATIC OF NETWORK NETWORK CALCULATION

POSSIBLE SCHEMATIC OF NETWORK NETWORK CALCULATION  
POSSIBLE SCHEMATIC OF NETWORK NETWORK CALCULATION  
POSSIBLE SCHEMATIC OF NETWORK NETWORK CALCULATION

412. 195/17.  
413. 1958/17.

[illegible][illegible][illegible]

100

[illegible]

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65  
66  
67  
68  
69  
70  
71  
72  
73  
74  
75  
76  
77  
78  
79  
80  
81  
82  
83  
84  
85  
86  
87  
88  
89  
90  
91  
92  
93  
94  
95  
96  
97  
98  
99  
100  
101  
102  
103  
104  
105  
106  
107  
108  
109  
110  
111  
112  
113  
114  
115  
116  
117  
118  
119  
120  
121  
122  
123  
124  
125  
126  
127  
128  
129  
130  
131  
132  
133  
134  
135  
136  
137  
138  
139  
140  
141  
142  
143  
144  
145  
146  
147  
148  
149  
150  
151  
152  
153  
154  
155  
156  
157  
158  
159  
160  
161  
162  
163  
164  
165  
166  
167  
168  
169  
170  
171  
172  
173  
174  
175  
176  
177  
178  
179  
180  
181  
182  
183  
184  
185  
186  
187  
188  
189  
190  
191  
192  
193  
194  
195  
196  
197  
198  
199  
200  
201  
202  
203  
204  
205  
206  
207  
208  
209  
210  
211  
212  
213  
214  
215  
216  
217  
218  
219  
220  
221  
222  
223  
224  
225  
226  
227  
228  
229  
230  
231  
232  
233  
234  
235  
236  
237  
238  
239  
240  
241  
242  
243  
244  
245  
246  
247  
248  
249  
250  
251  
252  
253  
254  
255  
256  
257  
258  
259  
260  
261  
262  
263  
264  
265  
266  
267  
268  
269  
270  
271  
272  
273  
274  
275  
276  
277  
278  
279  
280  
281  
282  
283  
284  
285  
286  
287  
288  
289  
290  
291  
292  
293  
294  
295  
296  
297  
298  
299  
300  
301  
302  
303  
304  
305  
306  
307  
308  
309  
310  
311  
312  
313  
314  
315  
316  
317  
318  
319  
320  
321  
322  
323  
324  
325  
326  
327  
328  
329  
330  
331  
332  
333  
334  
335  
336  
337  
338  
339  
340  
341  
342  
343  
344  
345  
346  
347  
348  
349  
350  
351  
352  
353  
354  
355  
356  
357  
358  
359  
360  
361  
362  
363  
364  
365  
366  
367  
368  
369  
370  
371  
372  
373  
374  
375  
376  
377  
378  
379  
380  
381  
382  
383  
384  
385  
386  
387  
388  
389  
390  
391  
392  
393  
394  
395  
396  
397  
398  
399  
400  
401  
402  
403  
404  
405  
406  
407  
408  
409  
410  
411  
412  
413  
414  
415  
416  
417  
418  
419  
420  
421  
422  
423  
424  
425  
426  
427  
428  
429  
430  
431  
432  
433  
434  
435  
436  
437  
438  
439  
440  
441  
442  
443  
444  
445  
446  
447  
448  
449  
450  
451  
452  
453  
454  
455  
456  
457  
458  
459  
460  
461  
462  
463  
464  
465  
466  
467  
468  
469  
470  
471  
472  
473  
474  
475  
476  
477  
478  
479  
480  
481  
482  
483  
484  
485  
486  
487  
488  
489  
490  
491  
492  
493  
494  
495  
496  
497  
498  
499  
500  
501  
502  
503  
504  
505  
506  
507  
508  
509  
510  
511  
512  
513  
514  
515  
516  
517  
518  
519  
520  
521  
522  
523  
524  
525  
526  
527  
528  
529  
530  
531  
532  
533  
534  
535  
536  
537  
538  
539  
540  
541  
542  
543  
544  
545  
546  
547  
548  
549  
550  
551  
552  
553  
554  
555  
556  
557  
558  
559  
560  
561  
562  
563  
564  
565  
566  
567  
568  
569  
570  
571  
572  
573  
574  
575  
576  
577  
578  
579  
580  
581  
582  
583  
584  
585  
586  
587  
588  
589  
590  
591  
592  
593  
594  
595  
596  
597  
598  
599  
600  
601  
602  
603  
604  
605  
606  
607  
608  
609  
610  
611  
612  
613  
614  
615  
616  
617  
618  
619  
620  
621  
622  
623  
624  
625  
626  
627  
628  
629  
630  
631  
632  
633  
634  
635  
636  
637  
638  
639  
640  
641  
642  
643  
644  
645  
646  
647  
648  
649  
650  
651  
652  
653  
654  
655  
656  
657  
658  
659  
660  
661  
662  
663  
664  
665  
666  
667  
668  
669  
670  
671  
672  
673  
674  
675  
676  
677  
678  
679  
680  
681  
682  
683  
684  
685  
686  
687  
688  
689  
690  
691  
692  
693  
694  
695  
696  
697  
698  
699  
700  
701  
702  
703  
704  
705  
706  
707  
708  
709  
710  
711  
712  
713  
714  
715  
716  
717  
718  
719  
720  
721  
722  
723  
724  
725  
726  
727  
728  
729  
730  
731  
732  
733  
734  
735  
736  
737  
738  
739  
740  
741  
742  
743  
744  
745  
746  
747  
748  
749  
750  
751  
752  
753  
754  
755  
756  
757  
758  
759  
760  
761  
762  
763  
764  
765  
766  
767  
768  
769  
770  
771  
772  
773  
774  
775  
776  
777  
778  
779  
780  
781  
782  
783  
784  
785  
786  
787  
788  
789  
790  
791  
792  
793  
794  
795  
796  
797  
798  
799  
800  
801  
802  
803  
804  
805  
806  
807  
808  
809  
810  
811  
812  
813  
814  
815  
816  
817  
818  
819  
820  
821  
822  
823  
824  
825  
826  
827  
828  
829  
830  
831  
832  
833  
834  
835  
836  
837  
838  
839  
840  
84

[illegible][illegible]

Year	1950	1951	1952	1953	1954	1955	1956	1957	1958	1959	1960
Population	1,000,000	1,050,000	1,100,000	1,150,000	1,200,000	1,250,000	1,300,000	1,350,000	1,400,000	1,450,000	1,500,000
Area	100,000	100,000	100,000	100,000	100,000	100,000	100,000	100,000	100,000	100,000	100,000
Population Density	10	10.5	11	11.5	12	12.5	13	13.5	14	14.5	15

	1970	1971	1972	1973	1974	1975	1976	1977	1978	1979	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076	2077	2078	2079	2080	2081	2082	2083	2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100	2101	2102	2103	2104	2105	2106	2107	2108	2109	2110	2111	2112	2113	2114	2115	2116	2117	2118	2119	2120	2121	2122	2123	2124	2125	2126	2127	2128	2129	2130	2131	2132	2133	2134	2135	2136	2137	2138	2139	2140	2141	2142	2143	2144	2145	2146	2147	2148	2149	2150	2151	2152	2153	2154	2155	2156	2157	2158	2159	2160	2161	2162	2163	2164	2165	2166	2167	2168	2169	2170	2171	2172	2173	2174	2175	2176	2177	2178	2179	2180	2181	2182	2183	2184	2185	2186	2187	2188	2189	2190	2191	2192	2193	2194	2195	2196	2197	2198	2199	2200	2201	2202	2203	2204	2205	2206	2207	2208	2209	2210	2211	2212	2213	2214	2215	2216	2217	2218	2219	2220	2221	2222	2223	2224	2225	2226	2227	2228	2229	2230	2231	2232	2233	2234	2235	2236	2237	2238	2239	2240	2241	2242	2243	2244	2245	2246	2247	2248	2249	2250	2251	2252	2253	2254	2255	2256	2257	2258	2259	2260	2261	2262	2263	2264	2265	2266	2267	2268	2269	2270	2271	2272	2273	2274	2275	2276	2277	2278	2279	2280	2281	2282	2283	2284	2285	2286	2287	2288	2289	2290	2291	2292	2293	2294	2295	2296	2297	2298	2299	2300	2301	2302	2303	2304	2305	2306	2307	2308	2309	2310	2311	2312	2313	2314	2315	2316	2317	2318	2319	2320	2321	2322	2323	2324	2325	2326	2327	2328	2329	2330	2331	2332	2333	2334	2335	2336	2337	2338	2339	2340	2341	2342	2343	2344	2345	2346	2347	2348	2349	2350	2351	2352	2353	2354	2355	2356	2357	2358	2359	2360	2361	2362	2363	2364	2365	2366	2367	2368	2369	2370	2371	2372	2373	2374	2375	2376	2377	2378	2379	2380	2381	2382	2383	2384	2385	2386	2387	2388	2389	2390	2391	2392	2393	2394	2395	2396	2397	2398	2399	2400	2401	2402	2403	2404	2405	2406	2407	2408	2409	2410	2411	2412	2413	2414	2415	2416	2417	2418	2419	2420	2421	2422	2
--	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	---

[illegible]

THE UNIVERSITY OF CHICAGO

```

SIMP= 0.70      CFS= 0.00      RTOR=12.20
DE(FEJO). DATA

```

U	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481	482	483	484	485	486	487	488	489	490	491	492	493	494	495	496	497	498	499	500										



1.02	4.70	56	2.8	0.0	2100.	1.02	17.30	131	0.00	0.00	0.00
1.02	4.70	57	0.3	0.0	2264.	1.02	14.00	132	0.00	0.00	0.00
1.02	4.70	58	0.9	0.0	2381.	1.02	14.30	133	0.00	0.00	0.00
1.02	4.70	59	0.4	0.0	2474.	1.02	14.00	134	0.00	0.00	0.00
1.02	4.70	60	0.2	0.0	2548.	1.02	14.30	135	0.00	0.00	0.00
1.02	4.70	61	0.6	0.1	2717.	1.02	23.00	136	0.00	0.00	0.00
1.02	4.70	62	0.1	0.1	3111.	1.02	20.30	137	0.00	0.00	0.00
1.02	4.70	63	0.8	0.1	3891.	1.02	21.00	138	0.00	0.00	0.00
1.02	4.70	64	0.1	0.1	5055.	1.02	21.30	139	0.00	0.00	0.00
1.02	4.70	65	0.1	0.1	6307.	1.02	22.00	140	0.00	0.00	0.00
1.02	4.70	66	0.3	0.1	7742.	1.02	23.30	141	0.00	0.00	0.00
1.02	4.70	67	0.4	0.1	8972.	1.02	21.30	142	0.00	0.00	0.00
1.02	4.70	68	0.3	0.1	9975.	1.02	21.30	143	0.00	0.00	0.00
1.02	4.70	69	0.3	0.1	11711.	1.02	0.00	144	0.00	0.00	0.00
1.02	4.70	70	0.8	0.1	11267.	1.02	0.00	145	0.00	0.00	0.00
1.02	4.70	71	0.5	0.1	11568.	1.02	1.00	146	0.00	0.00	0.00
1.02	4.70	72	0.2	0.1	11377.	1.02	1.43	147	0.00	0.00	0.00
1.02	4.70	73	1.13	0.1	1262.	1.02	2.30	148	0.00	0.00	0.00
1.02	4.70	74	1.17	0.1	12481.	1.02	2.30	149	0.00	0.00	0.00
1.02	4.70	75	1.17	0.1	12481.	1.02	3.00	150	0.00	0.00	0.00

50" 32.00 30.94 1.02 1875824.  
( 413.3) ( 75.7) ( 26.3) (18994.56)

PEAK	6-MIN	24-HOUR	72-HOUR	TOTAL VOLUME
74022.	44847.	21032.	7402.	1075021.
2119.	1254.	506.	212.	3334.
	10.43	2.89	0.41	15.73
	430.08	73.22	73.22	73.22
	2727.	4177.	4430.	4430.
	14037.	51467.	14000.	54990.

AVERAGES AND TOTAL VOLUMES FOR EACH 15 MINUTE

PEAK	6-MIN	24-HOUR	72-HOUR	TOTAL VOLUME
74022.	44847.	21032.	7402.	1075021.
2119.	1254.	506.	212.	3334.
	10.43	2.89	0.41	15.73
	430.08	73.22	73.22	73.22
	2727.	4177.	4430.	4430.
	14037.	51467.	14000.	54990.



PMF AND ONE-HALF PMF ROUTING

AD-A104 952

PRC CONSOER TOWNSEND INC ST LOUIS MO

F/G 13/13

NATIONAL DAM SAFETY PROGRAM. INCLINE VILLAGE LAKE DAM (MO 11041--ETC(U)

SEP 80 W G SHIFRIN

DACW43-80-C-0094

NL

UNCLASSIFIED

2 of 2

AD A  
104952

END  
DATE  
FILMED  
10-81  
DTIC

# HYDROGRAPH AT STA01001 FOR PLAN 1, R110.7

TIME	0.	5.	10.	15.	20.	25.	30.	35.	40.	45.	50.	55.	60.	65.	70.	75.	80.	85.	90.	95.	100.
STAGE	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70
DISCH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
INCHES	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
FEET	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
THOUS CU FT	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

TIME	0.	5.	10.	15.	20.	25.	30.	35.	40.	45.	50.	55.	60.	65.	70.	75.	80.	85.	90.	95.	100.
STAGE	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70
DISCH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
INCHES	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
FEET	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
THOUS CU FT	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

## HYDROGRAPH THROUGH TAILPIPE VILLAGE FOR (W. 11041)

### HYDROGRAPH DATA

TIME	0.	5.	10.	15.	20.	25.	30.	35.	40.	45.	50.	55.	60.	65.	70.	75.	80.	85.	90.	95.	100.
STAGE	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70	51.70
DISCH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
INCHES	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
FEET	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
THOUS CU FT	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0





510.8 517.5 516.6 515.8 515.1 514.7 514.1 513.8 513.5 513.2  
 510.9 517.6 516.7 515.9 515.2 514.6 514.0 513.6 513.3 513.0  
 510.4 510.8 510.0 510.7 510.7 510.7 510.7 510.7 510.7 510.7  
 510.7 510.7 510.7 510.7 510.7 510.7 510.7 510.7 510.7 510.7  
 510.7 510.7 510.7 510.7 510.7 510.7 510.7 510.7 510.7 510.7

PEAK 510.7 510.7 510.7 510.7 510.7 510.7 510.7 510.7 510.7 510.7

6-HOUR 74-HOUR 72-HOUR TOTAL VOLUME  
 27371 10730 2767 539504  
 767 297 106 19277  
 9.35 14.47 15.49 15.49  
 256.90 257.55 303.44 303.44  
 18474 23426 22224 22224  
 21094 24488 27409 27409

SUMMARY OF PMF AND ONE-HALF PMF FLOOD ROUTING

PEAK FLOW AND STORAGE (EWD 05 0 0 0) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS  
 FLOW IN CUMUL FEET PER SECOND (CUMUL METERS PER SECOND)  
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	SECTION	AREA	PLAN RATIO	RATIOS APPLIED TO FLOWS	
				1	2
HYDROGRAPH AT GILCO	1	17.2	1.0	7.442	17.11
		17.2	1.0	11.870	17.11
ROUTE 1	1	17.2	1.0	7.442	17.11
		17.2	1.0	11.870	17.11



# SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 .....	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 12.00 0.00 0.00	SPILLWAY CREST 110.70 58.00 3.00	TOP OF DAM 525.60 308.00 4372.00	MAXIMUM STORAGE ACFT 4517.0 961.0	MINIMUM OUTFLOW CFS 72740.0 55610.0	DURATION OVER TOP HOURS 4.00 0.00	TIME OF MAX OUTFLOW HOURS 41.00 41.00	TIME OF FAILURE HOURS 0.00 0.00
RATIO OF RESERVATION POT	1.00 0.20	1.00 523.71	1.00 523.71	1.00 523.71	1.00 523.71	1.00 523.71	1.00 523.71	1.00 523.71	1.00 523.71

PERCENT OF PMF FLOOD ROUTING  
EQUAL TO SPILLWAY CAPACITY

B-32

\*\*\*\*\*  
 FLOOD HYDROGRAPH PACKAGE (HEC-1)  
 DAN SAFETY VERSION JULY 1978  
 LAST MODIFICATION 26 FEB 79  
 \*\*\*\*\*

1	150	0	30	0	0	0	0	0
2	5							
3	1	4	1					
4	1							
5	1							
6	1							
7	1							
8	1							
9	1							
10	1							
11	1							
12	1							
13	1							
14	1							
15	1							
16	1							
17	1							
18	1							
19	1							
20	1							
21	1							
22	1							
23	1							
24	1							
25	1							
26	1							
27	1							

\*\*\*\*\*  
 DAN SAFETY INSPECTION - MISSOURI  
 INCLINE VILLAGE DAM (NO. 11041)  
 PERCENT PWF

1	0	0	0	0	0
2	0	0	0	0	0
3	0	0	0	0	0
4	0	0	0	0	0
5	0	0	0	0	0
6	0	0	0	0	0
7	0	0	0	0	0
8	0	0	0	0	0
9	0	0	0	0	0
10	0	0	0	0	0
11	0	0	0	0	0
12	0	0	0	0	0
13	0	0	0	0	0
14	0	0	0	0	0
15	0	0	0	0	0
16	0	0	0	0	0
17	0	0	0	0	0
18	0	0	0	0	0
19	0	0	0	0	0
20	0	0	0	0	0
21	0	0	0	0	0
22	0	0	0	0	0
23	0	0	0	0	0
24	0	0	0	0	0
25	0	0	0	0	0
26	0	0	0	0	0
27	0	0	0	0	0

\*\*\*\*\*  
 ROUTE HYDROGRAPH THROUGH INCLINE VILLAGE DAM (NO. 11041)  
 PERCENT PWF

1	0	0	0	0	0
2	0	0	0	0	0
3	0	0	0	0	0
4	0	0	0	0	0
5	0	0	0	0	0
6	0	0	0	0	0
7	0	0	0	0	0
8	0	0	0	0	0
9	0	0	0	0	0
10	0	0	0	0	0
11	0	0	0	0	0
12	0	0	0	0	0
13	0	0	0	0	0
14	0	0	0	0	0
15	0	0	0	0	0
16	0	0	0	0	0
17	0	0	0	0	0
18	0	0	0	0	0
19	0	0	0	0	0
20	0	0	0	0	0
21	0	0	0	0	0
22	0	0	0	0	0
23	0	0	0	0	0
24	0	0	0	0	0
25	0	0	0	0	0
26	0	0	0	0	0
27	0	0	0	0	0

\*\*\*\*\*

PREVIEW OF SEQUENCE OF SINFAM NETWORK CALCULATIONS

RANGE HYDROGRAPH AT 011041  
ROUTE HYDROGRAPH TO 011041  
END OF NETWORK

DATE - 4/23/19  
TIME - 11:04

14-00000 - 14-00000

[illegible]
$$A^{\alpha\beta} = \frac{1}{2}(\delta^{\alpha\beta} + \epsilon^{\alpha\beta}) \quad \text{and} \quad A^{\alpha\beta} = \frac{1}{2}(\delta^{\alpha\beta} - \epsilon^{\alpha\beta})$$

11  
12  
13  
14  
15  
16

50-447A RUBEN CUBELI, ILL.

2025 RELEASE UNDER E.O. 14176

[illegible][illegible]

SPEE	97	913	M4		842	872	872
6.00	25.00	10.00	116.00		120.00	10.00	0.00
***** DATA *****							

Variable	Mean	Standard deviation	Minimum	Maximum
PROB1	0.000	0.000	0.000	0.000
PROB2	0.000	0.000	0.000	0.000
PROB3	0.000	0.000	0.000	0.000
PROB4	0.000	0.000	0.000	0.000
PROB5	0.000	0.000	0.000	0.000
PROB6	0.000	0.000	0.000	0.000
PROB7	0.000	0.000	0.000	0.000
PROB8	0.000	0.000	0.000	0.000
PROB9	0.000	0.000	0.000	0.000
PROB10	0.000	0.000	0.000	0.000
PROB11	0.000	0.000	0.000	0.000
PROB12	0.000	0.000	0.000	0.000
PROB13	0.000	0.000	0.000	0.000
PROB14	0.000	0.000	0.000	0.000
PROB15	0.000	0.000	0.000	0.000
PROB16	0.000	0.000	0.000	0.000
PROB17	0.000	0.000	0.000	0.000
PROB18	0.000	0.000	0.000	0.000
PROB19	0.000	0.000	0.000	0.000
PROB20	0.000	0.000	0.000	0.000
PROB21	0.000	0.000	0.000	0.000
PROB22	0.000	0.000	0.000	0.000
PROB23	0.000	0.000	0.000	0.000
PROB24	0.000	0.000	0.000	0.000
PROB25	0.000	0.000	0.000	0.000
PROB26	0.000	0.000	0.000	0.000
PROB27	0.000	0.000	0.000	0.000
PROB28	0.000	0.000	0.000	0.000
PROB29	0.000	0.000	0.000	0.000
PROB30	0.000	0.000	0.000	0.000
PROB31	0.000	0.000	0.000	0.000
PROB32	0.000	0.000	0.000	0.000
PROB33	0.000	0.000	0.000	0.000
PROB34	0.000	0.000	0.000	0.000
PROB35	0.000	0.000	0.000	0.000
PROB36	0.000	0.000	0.000	0.000
PROB37	0.000	0.000	0.000	0.000
PROB38	0.000	0.000	0.000	0.000
PROB39	0.000	0.000	0.000	0.000
PROB40	0.000	0.000	0.000	0.000
PROB41	0.000	0.000	0.000	0.000
PROB42	0.000	0.000	0.000	0.000
PROB43	0.000	0.000	0.000	0.000
PROB44	0.000	0.000	0.000	0.000
PROB45	0.000	0.000	0.000	0.000
PROB46	0.000	0.000	0.000	0.000
PROB47	0.000	0.000	0.000	0.000
PROB48	0.000	0.000	0.000	0.000
PROB49	0.000	0.000	0.000	0.000
PROB50	0.000	0.000	0.000	0.000
PROB51	0.000	0.000	0.000	0.000
PROB52	0.000	0.000	0.000	0.000
PROB53	0.000	0.000	0.000	0.000
PROB54	0.000	0.000	0.000	0.000
PROB55	0.000	0.000	0.000	0.000
PROB56	0.000	0.000	0.000	0.000
PROB57	0.000	0.000	0.000	0.000
PROB58	0.000	0.000	0.000	0.000
PROB59	0.000	0.000	0.000	0.000
PROB60	0.000	0.000	0.000	0.000
PROB61	0.000	0.000	0.000	0.000
PROB62	0.000	0.000	0.000	0.000
PROB63	0.000	0.000	0.000	0.000
PROB64	0.000	0.000	0.000	0.000
PROB65	0.000	0.000	0.000	0.000
PROB66	0.000	0.000	0.000	0.000
PROB67	0.000			

$\text{JAVR NO} = -2.00$   $\text{FFRCS} = -1.00$   $\text{CCJ3J3} = 22.00$

DATE 06-09-2009 TIME 14:00

```

STRIP,=
0.00 PRECISION, DATA 0.00 RTIO,=10.00

```

DATE	TIME	WAVE	PERIOD	RAIN	EXC	LOSS	EXC	LOSS	COMP
END-OF-PERIOD FILE									
			COMP J	WAVE	PERIOD	RAIN	EXC	LOSS	COMP

[illegible]

U.S. DEPARTMENT OF THE ARMY  
OFFICE OF THE CHIEF OF STAFF  
WASHINGTON, D.C. 20315

3 AUG 1954

5 11.7

44711-3

•

•

100

B-36

COAST GUARD VESSEL, 11:14 AM, 5/15/77

•

(1) (2) (3) (4) (5) (6) (7) (8) (9) (10)

1955: 10

# SUMMARY OF DAM SAFETY ANALYSIS

CLASS I .....	ELEVATION STORAGE OUTLET	INITIAL VALUE 51.27 544 0.	SPILLWAY CREST 510.70 688 0.	TOP OF DAM 520.60 604 677.4	RATIO OF IMP	MAXIMUM STORAGE W. SAFETY	MAXIMUM STORAGE FC-FI	MAXIMUM OUTLET CFS	DURATION DOWN TO HOURLY	TIME OF WATER TO FLOW HOURS	TIME OF FAILURE HOURS
0.1	55.00	0.00	414.22	0.00	43.00	0.00	0.00	0.00	0.00	0.00	0.00
0.5	52.70	0.10	442.14	0.10	43.00	0.10	0.00	0.00	0.00	0.00	0.00
0.7	52.07	0.10	444.05	1.00	43.00	1.00	0.00	0.00	0.00	0.00	0.00
0.7	52.05	0.10	477.05	2.00	43.00	2.00	0.00	0.00	0.00	0.00	0.00



DA  
FILM  
O